

Final Report
Volume One - Executive Summary

Basewide Energy Study
Fort Indiantown Gap

DISTRIBUTION STATEMENT
Approved for public release
Distribution Unlimited

19971016 254



DEPARTMENT OF THE ARMY
CONSTRUCTION INSTITUTE, SHARE ENGINEERING GROUP, INC.
20 BAKER
CAMPUS V, LINDENWOOD, MO 63161

Project
Assessment TR-1 Library

17 Sep 1997

Based on NAW, these Energy Studies are unclassified/unlimited.
Distribution A. Approved for public release.

A handwritten signature in black ink, appearing to read "Marie Wakefield".

Marie Wakefield,
Librarian/Engineering

Final Report

Volume One - Executive Summary

**BASEWIDE ENERGY STUDY
FORT INDIANTOWN GAP**

Prepared for

**DEPARTMENT OF THE ARMY
Fort Indiantown Gap
Annville, Pennsylvania**

Prepared by

**XENERGY INC.
60 Mall Road
Burlington, Massachusetts**

June, 1989

TABLE OF CONTENTS

Section	Page
VOLUME I	
1 INTRODUCTION	1-1
1.1 Purpose	1-1
1.2 Scope of Work (SOW)	1-1
1.2.1 Increment A	1-1
1.2.2 Increment B	1-2
1.2.3 Increment F	1-2
1.2.4 Increment G	1-3
1.2.5 Project Documentation	1-3
2 EXISTING ENERGY CONSUMPTION	2-1
2.1 Introduction and Summary	2-1
2.2 Historical Energy Use	2-1
2.3 Energy End Use - FY 1985	2-3
2.4 Energy Fuel Use Breakdown - FY81 through FY85	2-3
2.5 Total Energy Use Trends	2-3
2.6 Individual Building Energy Use	2-5
3 ENERGY CONSERVATION OPPORTUNITY (ECO) SUMMARY	3-1
3.1 ECIP	3-1
3.2 CRIP and PECIP	3-1
3.3 Other Measures	3-4
3.4 Energy Management Control System: Evaluation	3-9
3.5 Conclusions, Recommendations & Energy Savings Plan	3-10
3.5.1 Conclusions	3-10
3.5.2 Recommendations & Energy Savings Plan	3-12

SECTION 1

EXECUTIVE SUMMARY

1.1 Purpose

The purpose of this Executive Summary is to summarize the results of the EBAP.

The Army Energy Plan, established in early 1978, sets both short and long term energy goals for the Army consistent with the Presidential Executive Order 12003 issued in mid-1977. It directs the Major Army commands to develop detailed implementation plans and funding documents. The National Energy Conservation Policy Act (NECPA) of 1978, directs that all facilities owned and operated by a Federal Agency must have all energy conservation retrofits performed by 1 January 1990.

The Department of the Army, through the Corps of Engineers Baltimore, has contracted with XENERGY Inc. to provide the Energy Engineering Analysis Program (EEAP) at Fort Indiantown Gap under contract number DACA31-85-0117. The results of the study are indicated in detail in the main report. Backup calculations have been provided under separate volumes to the Corps of Engineers.

1.2 Scope of Work (SOW)

The measurements of work to be provided as stated in the contract are as follows.

1.2.1 Increment A

Increment A projects involve modifying, improving or retrofitting existing buildings, including family housing, to make the buildings more energy efficient. Items to be investigated include architectural and structural features, HVAC systems, plumbing systems, interior or exterior building lighting.

Specifically, a matrix was created listing the 120 buildings to be included in the field survey along with the Energy Conservation Opportunities (ECO) to be examined. Not all buildings of the post were examined in this SOW, but instead, a majority of the energy consuming ones. Also, as specified in the ECO matrix, not every ECO was examined for each building since many were not applicable or appropriate. Despite this, many suitable energy conservation projects were formed at this post.

Computer modeling was used to incorporate field survey data, weather data, occupancy schedules, building construction data, energy distribution systems, and equipment data into a model of the typical buildings and to calculate total base energy use. The computer was used to develop load profiles, calculate energy savings, and evaluate possible energy conservation opportunities. The computer model was capable of analyzing the energy requirements of buildings, performance of heating, cooling, and ventilating equipment, energy distribution systems, and energy conversion equipment. The computer model was verified against historical energy use. The computer program analyzed the installation of an hour-by-hour basis. The computer model used was DOE-2 which has become the industry standard. It is comparable to the ULAST program used by the Army.

1.2.2 Increment B

Increment B projects involve utilities and energy distribution systems, EMCS for building and distribution systems, and existing energy plants. Specifically, the AE shall determine the feasibility of an EMCS for building electrical, mechanical and utility distribution systems. The intent of this study is to determine the basic conceptual architecture of the EMCS to the extent that primary economic calculations can be made to determine feasibility per ECTP criteria. The documentation shall be of sufficient accuracy to insure that future project design calculations that will be done after completion of this study will not deviate more than 20 percent from the results of this study.

The results of this increment indicate that a centralized EMCS is not recommended at Fort Indiantown Gap at this time since the SIR criteria is less than 1.0. Some 34 of the 120 buildings did qualify initially to be grouped into a system of automated controls, but taken as a whole, when the costs of centralizing and non-energy related costs were considered, failed to meet the SIR criteria. As technology and energy price changes in the future, a centralized EMS might be cost-effective.

1.2.3 Increment F

Increment F projects provide recommendations for modifications and changes in system operation which are within the Director of Engineering and Housing funding authority and management control. These projects are also referred to as low cost/no cost projects in this Scope of Work. The intent of this increment is to provide energy saving recommendations in the form of specific, practical instructions for the use by Director of Engineering and Housing personnel. The results of the study were that a number of ECOs were available for local action by the post. These include reduce lighting hours, downsize nozzles, remove vents, domestic hot water no cost/low cost, reconfigure DHW tank.

1.2.4 Increment G

Increment G projects are those feasible energy saving projects developed in Increments A and B which do not qualify under the ECIP criteria. Economic analysis shall be based on ECIP procedures.

The result of the study were that a few of the ECOs did not meet the ECIP criteria, namely reduce window area, drop ceiling with insulation convert to cool, T8 lamps and ballast and O&M.

1.2.5 Project Documentation

Finally, the SOW delineated that project documentation should be created for the following funding types: ECIP, PECIP and QRIP. After review with all parties concerned, five separate project documents have been created. In addition, other ECOs were grouped for local action only. Finally, ECOs are listed as not cost-effective as no projects were developed for these ECOs. These groupings are summarized in Table 1-1.

Table 1-1
ECO Grouping Summary

Project Type	ECOs
ORIP #1	Relamp/Refixture Lighting
PECIP #1	Heating Systems Controls New Burner Guns
PECIP #2	Destratification Fans
PECIP #3	Pipe and Duct Insulation
ECIP #1	Wall Insulation Roof Insulation Floor Insulation Caulk and Weatherstripping Storm Windows Replace Doors Storm Doors Door Seals Outside Air Reset Controls
Local Action Only (Increment F)	Reduce Lighting Hours Downsize Nozzles Remove Vents DHW No Cost/Low Cost Reconfigure DHW Tank
Not Cost-Effective (Increment G)	Reduce Window Area Drop Ceiling and Insulation Convert to Ceiling O&M T8 Lamps & Ballasts

SECTION 2

EXISTING ENERGY CONSUMPTION

2.1 Introduction and Summary

FIG uses four (4) different fuels to satisfy the energy input requirements of the facility. Fuels utilized are electricity, fuel oil (No. 2 and No. 6), propane and coal. During FY83, FIG's total consumption was 128,061 MBTU's. At the current total building inventory of 4,736,731 gross square feet, the facility consumption rate for FY83 was 39,703 BTU's/CSP/YR. When normalized for heating degree days recorded for the site in FY83, the consumption rate translates to 6.77 BTU's/CSP/HDD. A breakdown of units of fuels used at FIG which comprise the total consumption for FY81 through FY83 is shown in Table 2-1. An illustration of the percent of the total consumption each fuel type represents, for FY83 only, is shown in Figure 2-1.

An analysis of FIG's energy use has been conducted and is presented and summarized in Figures 2-1 through 2-3. A brief discussion of each figure is provided on page 2-3.

Figures 2-1 through Figure 2-3 have been plotted from the data shown in Table 2-1. The energy and building inventory area data shown in Table 2-1 is that which was provided by the Army for FIG.

Energy consumption data for FIG for the years FY 1973 through FY 1980 was unavailable.

2.2 Historical Energy Use

Table 2-1 summarizes the facility-wide energy data for fiscal years 1981 through 1983. Also listed are heating degree days base 65°F and the building inventory area data for the years addressed.

Table 2-1
Facility-Wide Energy Data for FY81 - FY85

Description	FY 1981	FY 1982	FY 1983	FY 1984	FY 1985
Electricity Usage (MBTU)	29,740	34,305	29,875	33,727	29,482
Fuel Oil Usage (MBTU)	111,420	120,968	112,549	96,818	96,395
Propane Usage (MBTU)	6,048	6,821	6,715	7,244	7,809
Coal Usage (MBTU)	17,101	38,944	38,201	46,302	51,285
TOTAL USE (MBTU)	164,309	202,871	187,340	181,091	188,661
Heating Degree Days	5,780	4,810	4,929	5,982	4,525
Square Footage (Ksf)	4,736.7	4,736.7	4,736.7	4,736.7	4,736.7
TOTAL USE (MBTU/Ksf)	34.69	42.82	39.55	38.23	39.70
TOTAL USE (BTU/M/HDD)	0.00600	0.00929	0.00602	0.00639	0.00677
Conversions:					
Electricity	3.413 MBTU/mWh				
Coal	25.4 MBTU/ton				
Propane	0.095 MBTU/gallon				
Fuel Oil (#2)	138,700 BTUs/gallon				
Fuel Oil (#6)	148,700 BTUs/gallon				

2.3 Energy End Use - FY 1985

Figure 2-1 illustrates the percent of the total consumption each fuel type represents. Electricity is used for lighting, fans, pumps, miscellaneous equipment and some cooling. Fuel oil is used for heating and domestic water heating, with most used for heating. Coal is used strictly for heating. Propane is used for domestic water heating and cooking. Space heating and domestic water heating consume 80.0% of the total energy use at FIG.

2.4 Energy Fuel Use Breakdown - FY81 through FY85

The graph in Figure 2-2 shows energy fuel use trends over the years studied. Propane and electricity use have remained fairly constant. Fuel oil consumption indicates a slow trend downward, as coal consumption rises. This illustrates the ongoing conversion of fuel oil-fired equipment to coal-fired equipment which apparently had been occurring over the five year period studied. Nonetheless, fuel use did increase between FY 1984 and FY 1985.

2.5 Total Energy Use Trends

The graph in Figure 2-3 presents the total energy use at FIG for 1981 through 1985 in MBTU's (left scale). For the five year period studied, the data indicates that energy use shows both increasing and decreasing trends year to year. Even when normalized by heating degree days as shown by the KBTU/s/HDD (right scale) the energy intensity does not show a clear increasing or decreasing trend.

Figure 2-1
Energy End-Use Breakdown (FY 1985)
Fort Indiantown Gap, Annville, PA




Figure 2-2
Energy Fuel Use Breakdown
Fort Indiantown Gap, Annville, PA





Figure 2-3
Total Energy Use
Fort Indiantown Gap, Annville, PA



2.6 Individual Building Energy Use

Table 2-2 presents individual building performance data for all 120 buildings plus the area 14 corridors audited for the study. The total KBTUs shown for each year for each building does include electricity consumed as estimated by the DOE-2 simulations. The KBTU/sf utilization shown for each building for FY85 includes what fuels are used in the building for space heating and domestic water heating and electricity. Data for the table was provided by actual fuel bills for each building and the estimated electrical use derived from the DOE-2 simulations.

The total FY1985 fossil fuel was 87,215 MBTU (55% of the past total) and the total electricity use was 3,944,920 kWh (46% of the past total). Also shown in Table 2-2 are the peak heating and cooling loads for each building, as well as the energy utilization index (KBTU/sf). The energy utilization index includes the fossil fuel and electrical use shown.

Table 2-2
Surveyed Building List Sorted by Building

Building Number	Building Description	Building Area (sq ft)	Annual Electricity Use (Kwh)	PY 1985 Fuel Use (MBTU)	Peak Heating Load (BTU/hr)	Peak Cooling Load (BTU/hr)	PY 1985 Energy Utilization (MBTU/sq ft)
00-001	Offices	14,884	108,154	2,421	322,43	615,88	137.76
00-004	BOQ	7,296	40,806	73	262,83	224,14	29.09
00-005	Club	12,686	31,970	127	438,81	373,90	25.11
00-010	Chapel	3,145	18,118	1,186	119,11	111,02	36.97
01-004	Administr.	2,592	5,261	300	98,86	91,00	122.44
03-108	Office	8,757	17,665	679	332,22	306,74	107.51
03-114	Clauses, n	2,532	32,573	473	94,04	125,13	259.01
04-117	Gym	21,927	127,572	1,872	1,141,49	760,32	106.79
04-118	Bowling Alley	11,234	22,714	1,233	428,43	394,40	124.67
04-142	STP	809	1,656	144	30,85	28,40	364.90
05-001	Office	2,146	15,950	813	76,29	60,60	399.93
05-002	Barracks	4,500	4,937	79	161,23	101,14	21.30
05-040	Office	1,070	1,174	66	43,10	24,05	65.43
05-047	Mess Hall	2,094	2,299	25	84,42	47,11	15.67
05-115	Office	34,710	161,195	39	1,173,27	1,023,03	15.11
05-117	Fire Station	5,469	40,118	810	192,33	152,81	172.21
07-001	Office	2,170	8,690	231	72,35	63,96	120.43
07-002	BOQ	7,353	54,973	1,219	259,59	207,45	110.86
07-004	Office	1,075	4,404	375	34,34	21,66	368.61
07-005	Office	2,222	13,614	290	79,49	62,37	199.83
07-006	Office	1,075	4,404	185	34,34	31,68	177.01
07-001	Motor Rpr	2,908	12,341	389	101,00	66,0*	211.10
07-004	Office	2,170	8,690	237	73,35	62,96	110.65
08-003	BOQ	7,354	30,127	651	248,58	216,75	102.31
08-004	Office	3,521	14,453	595	278,15	239,62	62.38
08-012	Office	2,167	10,913	243	82,83	77,20	162.63
08-013	Office	1,647	12,112	209	37,92	36,02	132.09
08-015	Office	1,647	10,833	241	35,76	33,61	167.74
08-020	Laundry	2,187	12,211	110	113,87	73,84	109.66
08-024	Office	783	3,758	136	27,54	21,88	224.33
08-027	Barracks	4,800	25,166	471	149,77	135,25	121.76
08-028	Barracks	4,800	26,233	330	234,31	151,93	341.44
08-032	Office	1,075	6,743	103	36,97	36,29	391.43
08-033	Barracks	4,830	75,166	382	149,77	134,23	148.42
08-034	Mess Hall	2,243	12,845	997	71,65	68,91	283.23
08-035	Barracks	4,800	25,166	340	149,77	134,23	139.09
08-036	Barracks	4,800	25,166	613	149,77	134,23	155.76
08-042	Office	1,075	4,404	313	36,34	31,64	367.01
08-046	Supply	2,435	4,946	205	94,08	84,50	120.56
08-048	Barracks	4,800	25,166	614	149,77	134,23	155.53
08-050	Barracks	4,800	25,166	395	149,77	134,23	106.67
08-051	Barracks	4,800	25,166	449	149,77	134,23	114.47
08-053	Barracks	4,800	25,166	666	149,77	134,23	173.35
08-054	Office	3,528	14,453	377	119,23	104,90	262.56
08-056	Lab	4,116	16,934	1,209	120,04	121,25	327.30
08-059	Motor Rpr	2,908	10,747	314	155,56	160,86	126.90
09-063	Benchboard	2,116	19,726	295	78,12	59,68	161.27
09-065	Club	13,962	76,729	2,572	604,53	583,64	177.54
09-067	BOQ	7,410	30,354	364	250,47	218,40	50.10
09-079	Library	4,319	19,309	264	132,72	103,16	72.42
10-030	Mess Hall	2,300	49,376	150	80,51	116,63	124.97
10-031	Barracks	6,720	30,732	426	179,03	233,26	164.20
10-032	Barracks	4,720	30,732	317	179,03	233,26	126.57

Table 2-2 (Continued)

Building Number	Building Description	Building Area (sq ft)	Annual Electricity Use (Kwh)	FY 1985 Fuel Use (BTU)	Peak Heating Load (BTU/hr)	Peak Cooling Load (BTU/hr)	FY 1985 Energy Utilization (BTU/sf)
10-013	Office	1,164	4,687	161	38.37	33.72	154.72
10-036	Supply	1,296	7,248	168	43.13	39.81	146.72
10-046	Warehouse	8,376	22,024	245	181.72	150.45	50.53
11-006	Clothing Sales	11,113	46,754	1506	578.63	275.21	156.93
11-007	Office	19,101	78,363	1513	645.76	343.05	95.22
11-009	Office	10,572	42,491	193	210.60	209.70	109.91
11-012	Supplies	11,107	45,502	5219	375.44	327.36	480.37
11-013	Storage	9,034	37,091	776	306.04	366.85	91.67
11-017	Shops	3,410	13,970	243	115.27	103.51	85.24
11-018	Shops	3,410	13,970	346	115.27	103.51	116.04
11-019	Office	5,399	22,921	658	189.13	164.91	131.39
11-029	Office	3,669	22,403	657	184.26	161.19	130.46
11-030	Shops	6,849	19,845	220	163.91	161.92	62.27
11-031	Storage	2,236	10,792	102	99.38	70.96	61.19
11-036	Lettuce	207	1,522	23	7.28	8.70	134.31
11-070	Heavy Equip	10,991	13,348	1,016	258.00	312.16	109.91
11-071	Warehouses	10,391	43,388	1,053	359.00	312.16	377.78
13-008	Cold Storage	40,000	294,133	280	1,404.70	1,117.68	32.17
13-091	Warehouses	119,200	469,321	3,906	4,079.22	3,513.26	63.53
14-095	Office	171	761	0	3.76	3.04	13.99
12-033	Mess Hall	1,449	1,809	165	66.42	37.08	103.80
12-038	Mess Hall	2,294	2,517	62	92.40	91.56	30.77
13-176	Caves Cr	2,574	12,373	332	97.49	90.86	143.39
14-099	Office	3,277	25,347	943	159.86	164.28	194.90
14-100	Office	3,070	4,207	940	117.00	107.78	109.31
14-101	BOQ	3,387	18,963	619	112.86	104.10	201.43
14-102	Civ Rm	1,075	1,604	196	34.34	31.68	194.31
14-103	BOQ	4,245	23,707	773	141.32	130.44	281.61
14-104	BOQ	3,975	24,940	725	206.97	154.21	203.20
14-105	BOQ	4,246	26,440	775	221.08	143.36	208.94
14-106	BOQ	3,391	21,275	619	176.56	114.46	208.96
14-107	BOQ	4,246	26,411	775	160.81	109.89	196.93
14-108	BOQ	3,391	21,275	619	174.36	114.49	208.96
14-109	BOQ	3,391	21,275	619	176.56	114.46	208.96
14-110	Office	3,700	17,798	675	160.14	130.61	196.84
14-111	BOQ	3,391	16,943	619	112.86	104.19	204.63
14-112	Office	3,848	11,028	761	167.91	126.91	192.21
14-116	Health Clinic	3,722	13,246	679	121.81	105.70	196.41
14-118	Health Clinic	2,967	11,315	666	93.33	81.56	196.49
14-120	Health Clinic	1,445	1,285	261	20.10	20.46	196.44
14-200	Office	4,097	16,794	748	134.49	120.75	196.53
14-208	Office	3,940	18,731	701	121.80	113.16	196.33
14-209	Office	3,849	18,731	701	120.87	113.18	196.33
14-206	Office	3,637	14,900	664	122.94	109.30	196.33
14-208	Office	3,637	14,900	664	122.94	109.30	195.33
14-210	Office	3,637	14,900	664	122.94	107.30	196.33
14-212	Storage	3,637	76,093	664	127.95	179.76	253.97
14-216	Office	3,346	18,751	701	123.80	113.10	196.33
14-300	Office	6,445	24,405	1,176	217.85	189.96	196.45
14-301	Storage	9,662	36,182	1,763	236.60	304.77	196.45
14-304	Computer	4,212	22,357	768	160.19	129.40	201.42
14-304	Office	3,637	14,900	664	122.94	107.30	196.33
14-308	Office	3,637	14,900	664	123.94	107.20	196.33
14-310	Storage	3,048	18,497	701	165.71	159.84	196.34

Table 2-2 (Concluded)

Building Number	Building Description	Building Area (sq ft)	Annual Electricity Use (Kwh)	FY1985 Fuel Use (MBTU)	Peak Heating Load (MBTU/hr.)	Peak Cooling Load (MBTU/hr.)	FY1985 Energy Utilization (MBTU/sq ft)
14-401	Central	762	16,361	743	29.44	34.65	224.27
14-413	Office	3,650	14,935*	466	122.34	107.58	196.45
14-417	Berger	3,632	14,883	469	122.30	107.08	196.48
14-419	Storage	1,650	14,953	466	122.38	107.58	196.45
14-501	Boiler Plant	2,872	26,474	705	136.17	108.19	207.43
16-COR	Area 14 Corridor	30,000	122,900	4,613	1,014.06	364.21	167.82
• 16-157	Office	3,006	12,313	386	101.61	88.60	109.79
• 16-162	DMP	11,043	122,700	2,011	634.60	304.20	136.54
• 16-153	Office	2,332	18,373	343	85.59	74.43	108.95
• 19-018	Office	2,088	19,023	369	78.97	73.40	145.42
• 19-020	Hanger	8,646	61,481	632	199.33	158.37	134.60
25-020	Office	761	3,026	57	36.08	21.84	131.39
TOTALS		70,665	3,944,530	87,331	27,319	131.37	

Note 1: Electricity use is not separately metered, values in table are derived from the DOE-2 simulations.

Note 2: Peak Heating and Peak Cooling Loads derived from the DOE-2 simulations.

Note 3: FY 1985 Energy Utilization includes both fossil fuel and electrical use.

Note 4: Shared (2) buildings had no record of FY1985 actual fuel use, table values derived from DOE-2 simu-

Note 5: Building 14-419 is presently vacant, fuel and electrical use based assumes full occupancy.

Note 6: Building 11-99 has electric heat only due to its small size.

Note 7: Area 14 buildings fossil fuel use presented by square footage accounting 25% central plant distribution

SECTION 3

ENERGY CONSERVATION OPPORTUNITY (ECO) SUMMARY

As a result of XENERGY's on-site evaluations and subsequent analysis, thirty Energy Conservation Opportunities (ECOs) have been evaluated. These include recommendations which address energy efficiency of the building envelope (walls, roof, windows), ventilation systems, HVAC system controls, alarm systems, domestic hot water (DHW) systems, and lighting systems.

Table 3-1 is the ECO Master Matrix Summary. This table shows the status of each of the recommendations for each of the buildings. Some of the codes in this table may require some additional clarification. Measures which are considered acceptable have a Savings to Investment Ratio (SIR) which is greater than 1 and are indicated as REC. If the SIR is less than 1, indicating that the measure is not recommended, we see SIR < 1. Finally, if the particular recommendation is not applicable to some building, we have indicated this by N/A.

All of the recommendations are further categorized as ECIP, QRIP or PECIP ECOs. Table 3-2 presents a list of the ECOs and indicates which category they represent. Local indicates that the measure is to be implemented by facility staff. A brief description of the categories follows.

3.1 ECIP

Recommendations which are classified as ECIP have payback periods which exceed 4 years and therefore are not available for funding by QRIP or PECIP. Primarily, these include building envelope recommendations such as roof, floor and wall insulation, caulking and weatherstripping, storm windows and doors, replacement doors, dock seals and outdoor air reset. The total energy savings of the ECIP recommendations is 18,082.9 MBtu including synergistic effects.

3.2 QRIP and PECIP

QRIP recommendations have paybacks which are less than 2 years. Included in this category are relamping and refixturing of incandescent and fluorescent lighting systems. Overall energy savings in the QRIP category are 808.37 MBtu.

Table 3-1
ECO Master Matrix Summary

યુદ્ધાચિત્ર (Cantabrigia)

Tabel 3-1 (Contd)

ટ્રાન્સફર (Transfer)

Table 3-1 (Continued)

Table 3-1 (Continued)

Table 3-2
ECO Summary Table

# ECO	Description	Electricity (kWh)	Fuel Oil #2 (gallons)	Coolant Oil (gallons)	Water (gallons)	Wastewater (gallons)	Chemical (gallons)	Solvent (gallons)	Gasoline (gallons)	Short Term Pollutants (gallons)	Long Term Pollutants (gallons)	
1	Delivery Selected Lighting Fixtures	91,277	0	0	2349	0.00%	\$8,400	\$1,000	\$57	0.1	\$0.0	
2	Chromate Neutral	0	0	0	778.5	0.00%	\$3,657	\$1,400	200	0.1	67.0	
3	Reactive Waste	2,677	0	157	764.9	0.00%	\$0,000	\$7,000	100	0.0	0.0	
4	Reactive Lighting Fixture	30,270	0	0	167.2	0.00%	\$1,053	\$1,000	100	0.0	0.0	
5	DRIP Hot/Cold Water Cols	17,972	632	0	100	100.7	\$1,075	\$0,344	200	0.0	0.0	
6	Reactive Drip/Waste Tank	3,746	0	0	80	21.1	0.00%	\$27.00	21.170	4.0	2.0	
7	Reactive Intermediate w/ Phenomen	108,227	0	0	60	440.5	\$1,112	\$26,320	\$1,436	1.6	6.0	
8	Reactive Pharmaceutical Lighting	60,844	0	0	60	105.0	\$1,240	\$11,700	647	3.2	2.4	
9	Reactive Other Chem	0	20,307	0	25.0	4,000.0	\$19,356	\$1,000	100	2.0	0.0	
10	Reactive Heating System Controls	0	54,749	20,373	0	11,564.3	\$0,401	\$16,570	\$1,000	2.4	3.6	
11	Direct Connection Piping	7,882	2,055	0	50	50.2	0.00%	\$1,465	\$0,177	3.0	4.1	
12	Pipes & Duct Insulation	0	51,681	0	0	0.00	\$1,274.00	\$0,000	2.0	4.0	0.0	
13	Cables & Wires/Hosing	32,754	14,214	17,677	37.6	5,579.6	0.00%	\$25,716	\$20,602	310,000	9.0	
14	Sealant/Adhesive	0	1,114	203	0.0	217.7	0.00%	\$2,400	\$11,104	541.1	3.2	
15	Duct Seal	0	0	0	2.0	182.2	0.00%	\$0.00	\$0.00	11.3	1.7	
16	Booster Domes	0	5,345	8,300	0.0	2,891.0	2.00%	\$0,700	\$7,700	94,236	2.5	
17	Summer Windows	226	0	6,428	26.4	2,965.5	2.00%	\$1,162	\$10,015	58,057	1.0	
18	Winter Windows	0	7,238	12,156	9.1	3,131.5	3.00%	\$15,464	\$27,507	502,007	14.7	
19	Power Insulators	117	0	0	0.00	0.00	0.00%	\$0,000	\$0,000	0.0	0.0	
20	Oil-Based Coatings	0	242	0	0	1.65	0.00%	\$33.00	\$0,000	10.1	1.0	
21	Paint Insulators	62	5,239	0	0.00	2.5	1,000.5	1.00%	\$2,342	\$144,204	59,046	17.0
TOTALS												
		361,771	144,227	87,569	255.3	67,213	54,516	\$51,201	\$15,729	462,346	5.9	

Notes:

1. Construction costs are for fiscal year 1992 and do not include ECOF, design, or construction.

2. Surcharges for ECOF project include allowances for synergistic effects.

3. Short term ECOF contributions from new ECOs (solid and liquid waste).

4. Cost to Wiesenthalberg ECO contribution from ECOA (allowance for construction).

5. Total savings for ECOF Project is \$477,111.

PECIP recommendations are those with paybacks under 4 years. These are further reduced into PECIP #1, PECIP #2, and PECIP #3. PECIP #1 includes heating system control improvements and installation of new burner guns. The energy savings are 13,961.9 MBtu. PECIP #2 includes destratification fans and represents an energy savings of 369.2 MBtu. PECIP #3 includes installation of pipe and duct insulation and results in energy savings of 8,136.2 MBtu.

3.3 Other Measures

Certain measures are referred to as local indicating that facility staff will handle implementation. The recommendations listed as local include reduced lighting hours, de-lamping of light fixtures, downgrading nozzles, reconfiguration of DHW systems, no cost/low cost DHW measures, remove vents and installation of T8 lamps and ballasts.

Deleted ECOs are those measures do not qualify ($STR < 1$) for any buildings. Conversion to cool and reduced window area fell into this category.

3.4 Energy Management Control System Evaluation

An Energy Management Control System (EMCS) was evaluated at Fort Indiantown Gap and a conceptual design developed.

Each building and its energy-consuming systems was analyzed to determine the applicability of various energy conservation measures as well as EMCS. All of the pertinent data were obtained from field investigation and documentation.

The savings were analyzed for the functions of temperature reset, load shedding, HVAC improvements and reduction of lighting hours using conventional controls such as timers. As per the SOW alternative local control methods of implementing were also evaluated against the EMCS. The EMCS analysis and conceptual design was done in accordance with TM-3-815-2/NAVPAC DM-9/AFM 88-36.

Costs were computed using the guidelines from HNDSF 83-010-ED-M3 increased by 7.4 percent to reflect price increases since January 1, 1986 the date upon which the guidelines were based. The local HVAC improvement costs, such as radiator valves, were added to the individual building costs.

Savings and EMCS field costs were computed for each building. As per the Army documented analysis method all buildings with an SIR of less than one were excluded from the final EMCS package. To the EMCS building field costs were added the central equipment, DTM and general costs.

The resultant EMCS considered provided monitoring and/or control functions in 34 buildings. A total of 276 points would be required for implementation. According to NAVFAC DM-4.9/AFM 88-36 a small EMCS would not be appropriate since more than 125 points are required. Since the cost difference between a small system (50 - 600 points) and a medium system (200 - 2,500) is about 12% and yet provides for significant expansion, the medium system was analyzed. Finally, the SOW required an EMCS system having the capacity to provide expanded control throughout the Base in the future.

Table 3-3 presents a summary of costs for the larger, medium, and small EMCS systems in addition to the energy and cost savings. Because the facilities were generally quite small and had such a small number of points per building, the savings were not large enough to justify the costs of an EMCS. The SIR for the medium EMCS system was .87. Even when evaluating a small EMCS the SIR still was less than 1 at .86.

3.5 Conclusions, Recommendations & Energy Savings Plan

3.5.1 Conclusions

The following conclusions were reached as a result of the Energy Engineering Analyses Program (EEAP) Basewide Energy Study at FIC:

1. Currently, there is significant energy waste at the post in both fossil fuels and electricity. This is due to the age and construction of the buildings.
2. No major energy conservation project or efforts have been instituted at the post. In fact, that is one reason why this EEAP has been completed.
3. Of the buildings surveyed, there is significant energy conservation opportunities (ECOs) for all major end-use categories and fuels. If all ECOs are implemented, it is estimated that 34.5% of the energy will be saved. This includes allowances for synergistic effects.
4. These ECOs have been grouped into five major projects plus local action for implementation by the Army.

Table 3-3
Final Cost Summary

Energy Management and Control System
HNDSP 83-048-EDME APRIL 1987

Pknts: 276

	Large	Medium	Small
COSTS:			
General Costs	\$72,017	\$72,017	\$71,681
System Equipment:	\$148,295	\$101,902	\$50,117
Software	\$68,319	\$60,633	\$41,656
Field Equipment	\$350,581	\$350,581	\$350,581
Data Trans Media	\$49,233	\$49,233	\$48,233
Maintenance(40%)	\$45,305	\$41,662	\$37,189
Taxes and Insurance	\$51,483	\$47,570	\$42,261
Overhead	\$102,967	\$95,140	\$84,822
Profit	\$68,644	\$63,427	\$56,348
Bond	\$6,864	\$6,343	\$5,635
TOTAL COSTS:	\$861,709	\$888,608	\$789,431

SAVINGS:		
Electricity	16,331 kWh	mmbtus
Coal	43 tons	1,095
Oil	47,068 gallons	6,528
Oil	17,234 gallons	2,880
TOTAL		10,259 \$91,271

BIR 0.70 0.76 0.86

3.5.2 Recommendations & Energy Savings Plan

It is recommended that all the ECOs which met the cost-effectiveness criteria (ECIP criteria) be funded and implemented. Twenty-one different ECOs were shown to be cost-effective and are summarized in Table 3-2 below. The table lists for each ECO the specific fuel savings, the savings in MBTU, savings as a percent of the total energy use of the building surveyed, savings in current dollars, estimated construction cost, SICOH, simple payback, and the savings-to-investment ratio (SIR). Also listed is the recommended grouping of the ECOs.

It is recommended that five projects (plus local action) be implemented as follows:

Project	ECOs
QRIP #1	Refixture Incandescents w/ Fluorescent Relamp Fluorescent Lighting
PECIP #1	Install New Burner Guns Improve Heating System Controls
PECIP #2	Install Desratification Fans
PECIP #3	Install Pipe & Duct Insulation
ECIP #1	Caulk & Weatherstripping Storm Doors Dock Seals Replace Doors Add Storm Windows Install Wall Insulation Install Floor Insulation Outside Air Reset Controls Install Roof Insulation
Local Action	Relamp Selected Lighting Fixtures Downsize Burner Nozzles Remove Vents Reduce Lighting Hours DHW No Cost/Low Cost Reconfigure DHW Tank

It is further recommended that the local action ECOs be implemented during FY1990. It is recommended that the QRIP and PECIP projects be implemented as soon as possible either during FY1991 or FY1992. Because of the size of the ECIP project, it is recommended that implementation be funded during FY1996.